



Maharaja Ranjit Singh Punjab Technical University
Dabwali Road, Bathinda.

(Established by Govt. of Punjab vide Punjab Act No. 5 of 2015)

Ref. No. MRSPTU/EST/17-18/ 7131 to 7136

Dated 10/11/17

(Regd.)

To

As per List Attached.

Sub: - Quotations for Providing & Laying of paver blocks 60mm thick at PIT GTB Garh Moga.

Dear Sir,


01. You are requested to quote the rates for the items shown in the Appendix 'A' attached to this letter.
02. Following shall be taken note of while quoting the rates:-
 - a) The rates will be F.O.R. PIT, GTB Garh Moga.
 - b) Quotation received later than due date are liable to be ignored/rejected.
 - c) Quotation must be submitted on letter head of the firm with all particular, any other format will not be acceptable.
 - d) The quality of the items to be quoted should be best available in the market.
 - e) The envelope must bear the word:-

"QUOTATION FOR " Providing & Laying of paver blocks 60mm thick at PIT GTB Garh Moga.

Enquiry No. As above dated _____
Due on 20-11-2017.

IMPORTANT: -In the absence of information as required under 2(e) above, if an envelope is received & opened inadvertently, the university will not be responsible and the quotation may not be considered even if quoting lowest rates.

03. The quotations duly completed, should be in the name of Executive Engineer, MRSPTU, Bathinda and should reach in the **office of undersigned by 20-11-2017 up to 03:30** and same shall be opened at **04:00** on same date. Your representative may be present during the opening of the quotations.


Executive Engineer,
MRSPTU, Bathinda.

Copy to:-

1. Incharge, Computer Centre, to upload a copy on university & college websites.
2. Master File

P.T.O.

TERMS & CONDITIONS

1. **DELIVERY PERIOD:-**

Minimum Period for delivery/job completion should be mentioned clearly.

2. **VALIDITY OF QUOTATIONS:-**

Quotations will be considered valid for 03 months from the date of quotation.

3. **GUARANTEE/WARRANTY:-**

Guarantee/Warranty should be mentioned clearly.

4. **DISCOUNT/REBATES:-**

A Special discount/rebate wherever admissible keeping in view that the supplies are being made for education purpose in respect of Public Institution of national importance may please be indicated.

5. **VICE CHANCELLOR'S RIGHTS:**

Vice Chancellor, MRSPTU, Bathinda reserves the rights of acceptance or rejection of any or all quotations. The discretion for increasing or decreasing of the quantities also rests with him. MRSPTU also not bind itself to accept the lowest price. In case of any dispute, the decision of Vice Chancellor, MRSPTU, Bathinda will be final & binding.

6. **SAMPLE/BRAND/MAKE/WEIGHT:-**

Sample where asked for, will invariably be made available and sent along with the quotations. However, Brand/Make/Weight etc. must be mentioned clearly in the quotations. Technical literature/pamphlet should also be enclosed.

7. **REJECTION:-**

Quotation not conforming to the set procedure as above will be rejected.

8. **CORRESPONDANCE:**

No correspondence regarding acceptance/rejection of a quotation will be entertained.

MRSPTU shall not be held responsible for any postal delay in sending or late receipt of quotation. Quotation should be free from corrections & erasures.



Appendix-'A'

MAHARAJA RANJIT SINGH PUNJAB TECHNICAL UNIVERSITY,
DABWALI ROAD, BATHINDA
(Established by Govt. of Punjab vide Punjab Act No.5 of 2015)

Providing & Laying of paver blocks 60mm thick at PIT GTB Garh Moga

S.No.	Description of Items	Qty. (approx.)	Unit	Rate
1/6.6	Earth work in excavation in foundations, trenches etc. in all kinds of soil where pick jumper work is not involved and not exceeding 2.0 meters depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation.	8	Cum.	
2/NS	Earth Filling brought from outside	20	Cum	
3/11.5	First class burnt brick work laid in cement sand mortar 1:5 in foundation and plinth.	6.80	Cum.	
4/10.8 (b) (ii)	Cement Concrete 1:5:10 with stone ballast 40mm gauge using Concrete Mixer volumetric type	19	Cum.	
5/14.155	Providing and laying 60 mm thick cement concrete interlocking paver block of M-35 grade machine made rubber moulded smooth finish by strong vibratory process or with vibro-hydraulic compaction machine and of approved size and design / shape laid in Ordinary Grey Colour and pattern over and including 40 mm thick compacted bed of coarse sand, filling the joints with fine sand etc, all complete as per directions of Engineer-in-Charge for Light Traffic Areas such as Pedestrian plazas, shopping complexes, ramps, car parks, office driveways, housing colonies, office complexes, rural roads with low volume traffic, farm houses, beach sites, tourist resorts, local authority footways, residential roads, etc. (A&C slip II)	166	Sqm	
6/15.9	12.5 mm thick plaster 1:4	30	Sqm.	
7/10.12 ii)	Cement Concrete 1:2:4 with stone ballast of size 20 mm guage using concrete mixer volumetric type complete as per PWD specifications	0.60	Cum	
8/28.13 xv)	Providing, Laying, Fixing & Jointing of P.V.C pipes as per ISI- 4985 (ISI marked with the prior approval of Engineer-in-charge) along the Trenches and laying the same in trenches to correct alignment and gradients, cutting, jointing and testing complete as per specifications 110mm o/d pipe of 6 kgf./ sqcm	9.14	Mtr	

Note:- Quantity may vary at the time of execution of work.

Specifications Checked & Verified.


**Executive Engineer,
MRSPTU, Bathinda.**