



**Maharaja Ranjit Singh Punjab Technical University**  
**Dabwali Road, Bathinda.**

(Established by Govt. of Punjab vide Punjab Act No. 5 of 2015)

Ref. No. MRSPTU/EST/17-18/ 6036 to 6042

Dated 17/8/17

(Regd.)

To

As per List Attached.

**Sub: - Quotations for Providing & Fixing MS Place identification Sign Board 24' x 4' on roof top, main gate and Direction Sign Board 1200mm x 1800mm on Road Side at PIT, Nandgarh.**

Dear Sir,

01. You are requested to quote the rates for the items shown in the Appendix 'A', 'B' and 'C' separately attached to this letter.
02. Following shall be taken note of while quoting the rates:-
  - a) The rates will be F.O.R. PIT, Nandgarh.
  - b) Quotation received later than due date are liable to be ignored/rejected.
  - c) Quotation must be submitted on letter head of the firm with all particular, any other format will not be acceptable.
  - d) The quality of the items to be quoted should be best available in the market.
  - e) The envelope must bear the word:-

**"QUOTATION FOR " Providing & Fixing MS Place identification Sign Board 24' x 4' on roof top, main gate and Direction Sign Board 1200mm x 1800mm on Road Side at PIT, Nandgarh.**

Enquiry No. As above dated \_\_\_\_\_  
Due on 04-09-2017.

**IMPORTANT:** -In the absence of information as required under 2(e) above, if an envelope is received & opened inadvertently, the university will not be responsible and the quotation may not be considered even if quoting lowest rates.

03. The quotations duly completed should be in the name of Executive Engineer, MRSPTU, Bathinda and should reach in the **office of undersigned by 04-09-2017 up to 03:30** and same shall be opened at **04:00** on same date. Your representative may be present during the opening of the quotations.

Executive Engineer,  
MRSPTU, Bathinda.

Copy to:-

1. Incharge, Computer Centre, to upload a copy on university & college websites.
2. Master File

P.T.O.

## **TERMS & CONDITIONS**

1. **DELIVERY PERIOD:-**

Minimum Period for delivery/job completion should be mentioned clearly.

2. **VALIDITY OF QUOTATIONS:-**

Quotations will be considered valid for 03 months from the date of quotation.

3. **GUARANTEE/WARRANTY:-**

Guarantee/Warranty should be mentioned clearly.

4. **DISCOUNT/REBATES:-**

A Special discount/rebate wherever admissible keeping in view that the supplies are being made for education purpose in respect of Public Institution of national importance may please be indicated.

5. **VICE CHANCELLOR'S RIGHTS:**

Vice Chancellor, MRSPTU, Bathinda reserves the rights of acceptance or rejection of any or all quotations. The discretion for increasing or decreasing of the quantities also rests with him. MRSPTU also not bind itself to accept the lowest price. In case of any dispute, the decision of Vice Chancellor, MRSPTU, Bathinda will be final & binding.

6. **SAMPLE/BRAND/MAKE/WEIGHT:-**

Sample where asked for, will invariably be made available and sent along with the quotations. However, Brand/Make/Weight etc. must be mentioned clearly in the quotations. Technical literature/pamphlet should also be enclosed.

7. **REJECTION:-**

Quotation not conforming to the set procedure as above will be rejected.

8. **CORRESPONDANCE:**

No correspondence regarding acceptance/rejection of a quotation will be entertained.

MRSPTU shall not be held responsible for any postal delay in sending or late receipt of quotation. Quotation should be free from corrections & erasures.



**Appendix-'A'**

**MAHARAJA RANJIT SINGH PUNJAB TECHNICAL UNIVERSITY,  
DABWALI ROAD, BATHINDA**

(Established by Govt. of Punjab vide Punjab Act No.5 of 2015)

**Providing & Fixing MS Place Identification Sign Board 24'x4' on roof top at PIT Nandgarh**

S.No.	Description of Items	Qty. (approx.)	Rate
1/18.7	Structural steel work in compound built up girders or stanchions built up from two or more R.S. joists or channel section or plates and angles etc. riveted or welded, including cutting and fixing all lattices bars, stiffeners, gusset, plates, bolts nuts, rivets, welding rods, etc. complete with flange plates, heads sole plates, angle connections, etc. with hoisting and erecting in position.	4 Qtl	
2/16.21	Applying priming coat with metal primer on new steel or iron work including preparation of surface. a) With special quality paint	20 Sqm	
3/16.22	Painting two coats excluding priming coat with ready mixed paint for metallic surfaces in all shades on steel or iron work a) With special quality paint	20 Sqm	
4/ 16.48	Painting new letters and figures of black synthetic enamel paint to an even shade With ordinary quality paint	105 cm ht X 35 No's	
5/NS	Painting/ Printing Logo as per requirements at site	1 Job	
6/NS	Carriage/ Installation/ Alignment/ Labour Charges as per site requirements	01 No	
7/NS	Providing, Fixing & Testing of LED Flood Light 30 Watt Make- Havell's/ Bajaj/ Philip's	02 No's	
8/NS	Providing, Fixing & Testing of Timer, Contactor & MCB DP 25 Amp Curve C fitted in sheet metal Powder coated distribution board (dust protected) with required wiring in 1.5mmsq copper wire in PVC pipe complete in all respect	01 No	
9/33.10 D ii)	XLPE/ PVC INSULATED UN-ARMOURED CABLES (LOOSE IN THE EXISTING TRENCH OR PIPE): Supply and laying of XLPE/ P.V.C. insulated P.V.C. sheathed aluminium conductor un-armoured cable working voltage upto and including 1100 volts grade to be laid loose in the existing trench or pipe as per PWD General Specifications (Electrical Works):- XLPE/ PVC insulated PVC sheathed aluminium conductor unarmoured cable working voltage 1100volts grade 10sq.mm (Twin Core)	40 Mtr	
10/33.3 7 i)	DOUBLE WALLED CORRUGATED (DWC) HDPE PIPES: Supply and erection of double walled corrugated (DWC) HDPE pipe to be laid 1mtr. below ground level including excavation (making necessary trench), placing the pipe in position and back filling with excavated soil etc. of the required size. Double walled corrugated (DWC) HDPE pipe 50/ 38mm (outer/ inner dia.)	40 Mtr	
11/10.8 (a)	Cement concrete 1:5:10 with 40 mm gauge brick ballast	0.29 Cum	
12/10.1 2 (ii)	Cement concrete 1:2:4 with stone ballast or shingle using Concrete Mixer volumetric type	1.81 cum	
13/9.1	Shuttering for faces of concrete foundations and foundation beam & plinth beam (vertical or battering)	11.89 Sqm.	
Total			

Note:- Quantity may vary at the time of execution of work.

Specifications Checked & Verified.

Executive Engineer,  
MRSPTU, Bathinda.



Appendix-'B'

**MAHARAJA RANJIT SINGH PUNJAB TECHNICAL UNIVERSITY,**  
**DABWALI ROAD, BATHINDA**  
(Established by Govt. of Punjab vide Punjab Act No.5 of 2015)

**Providing & Fixing MS Place Identification Sign Board 24'x4' on Main Gate at PIT Nandgarh**

S.No.	Description of Items	Qty. (approx.)	Rate
1/18.7	Structural steel work in compound built up girders or stanchions built up from two or more R.S. joists or channel section or plates and angles etc. riveted or welded, including cutting and fixing all lattices bars, stiffeners, gusset, plates, bolts nuts, rivets, welding rods, etc. complete with flange plates, heads sole plates, angle connections, etc. with hoisting and erecting in position.	5.25 Qtl	
2/16.21	Applying priming coat with metal primer on new steel or iron work including preparation of surface.	20 Sqm	
a)	With special quality paint		
3/16.22	Painting two coats excluding priming coat with ready mixed paint for metallic surfaces in all shades on steel or iron work	20 Sqm	
a)	With special quality paint		
4/ 16.48	Painting new letters and figures of black synthetic enamel paint to an even shade With ordinary quality paint	105 cm ht X 35 No's	
5/NS	Painting/ Printing Logo as per requirements at site	1 Job	
6/NS	Carriage/ Installation/ Alignment/ Labour Charges as per site requirements	01 No	
7/NS	Providing, Fixing & Testing of LED Flood Light 30 Watt Make- Havell's/ Bajaj/ Philip's	02 No's	
8/NS	Providing, Fixing & Testing of Timer, Contactor & MCB DP 25 Amp Curve C fitted in sheet metal Powder coated distribution board (dust protected) with required wiring in 1.5mmsq copper wire in PVC pipe complete in all respect	01 No	
9/33.10 D ii)	XLPE/ PVC INSULATED UN-ARMOURED CABLES (LOOSE IN THE EXISTING TRENCH OR PIPE): Supply and laying of XLPE/ P.V.C. insulated P.V.C. sheathed aluminium conductor un-armoured cable working voltage upto and including 1100 volts grade to be laid loose in the existing trench or pipe as per PWD General Specifications (Electrical Works):- XLPE/ PVC insulated PVC sheathed aluminium conductor unarmoured cable working voltage 1100volts grade 10sq.mm (Twin Core)	40 Mtr	
10/33.37 i)	DOUBLE WALLED CORRUGATED (DWC) HDPE PIPES: Supply and erection of double walled corrugated (DWC) HDPE pipe to be laid 1mtr. below ground level including excavation (making necessary trench), placing the pipe in position and back filling with excavated soil etc. of the required size. Double walled corrugated (DWC) HDPE pipe 50/ 38mm (outer/ inner dia.)	40 Mtr	
11/10.8 (a)	Cement concrete 1:5:10 with 40 mm gauge brick ballast	0.29 Cum	
12/10.12 (ii)	Cement concrete 1:2:4 with stone ballast or shingle using Concrete Mixer volumetric type	1.81 cum	
13/9.1	Shuttering for faces of concrete foundations and foundation beam & plinth beam (vertical or battering)	11.89 Sqm.	
Total			

Note:- Quantity may vary at the time of execution of work.

Specifications Checked & Verified.

Executive Engineer,  
MRSPTU, Bathinda.



Appendix-'C'

**MAHARAJA RANJIT SINGH PUNJAB TECHNICAL UNIVERSITY,  
DABWALI ROAD, BATHINDA**

(Established by Govt. of Punjab vide Punjab Act No.5 of 2015)

**Providing & Fixing Advance Direction Sign Board 1200mm x 1800mm on Road Side at  
PIT Nandgarh**

S.No.	Description of Items	Qty. (approx.)	Rate
1/24.48 d)	Advance Direction Sign Board 1200x1800mm Rectangular Advance Direction sign board 1200x1800mm rectangular as per IRC 67-2001 with retro reflective high intensity microprismatic grade sheeting fixed over 2mm thick aluminium sheet with 25x25x3mm angle iron frame supported on two mild steel angle iron posts 65x65x6mm firmly fixed to ground in foundation concrete 1:2:4 of size 0.60x0.60x0.75m for vertical post complete as per technical clause 801 of MORT&H specifications	01 No	
Total			

Note:- Quantity may vary at the time of execution of work.

**Specifications Checked & Verified.**

**Executive Engineer,  
MRSPTU, Bathinda.**