

## Annexure-A

### Renovation/ False Ceiling in Architecture Deptt, Library & ECE Deptt. etc.

S. No.	Description of Items	Qty. (approx)	Unit	Rate	Total Amt
1/15.9	12.5 mm thick cement plaster 1:4	22	Sqm	118.16	2599.52
2/16.3	White washing (Three coat)	198	Sqm	10.90	2158.20
3/16.18 b)	Painting two coats excluding priming coat with synthetic enamel paint in all shades on wood work, metallic or plastered, concrete surface to give an even shade. With ordinary quality Paint	12	Sqm	49.48	593.76
4/16.21 b)	Applying priming coat with metal primer on new steel or iron work including preparation of surface. With ordinary quality Paint	12	Sqm	16.26	195.12
5/17.43 c)	P/F Hydraulic door closer ISI Mark compete in all respects	04	No's	1131.32	4525.28
6/NS	Removing old false Ceiling & Stacking of its materials away from site.	150	Sqm	20.00	3000.00
7/NS	Providing and fixing of false ceiling at all heights of 595x595x8mm Mineral Fibre ceiling tiles in grid system. The frame work comprise of made of GI 120 GSM coating with minimum 0.3mm thickness main runner spaced at 1200mm centre to centre securely fixed to the structural soffit by approved hangers at 1200mm maximum centres. Hangersa (GI wire of 4mm dia) to be fixed by approved roof plug, level adjusters and screw etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centres to form 1200x600mm modules. Cut across tees longer than 600mm to be supported independently. 600x600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to walls at 450mm maximum centres complete in all respects as per specifications	390	Sqm.	865.00	337350.00
8/14.133	Providing and laying vitrified floor tiles 600x600mm size premium quality, manufactured using Soluble Salt Technology, with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and shades, laid on existing flooring laid with cement based high polymer modified quick set tile adhesive (water based) of approved make IS 15477 marked using 5 Kg adhesive per sqm of tile area in average 3mm thickness over existing base etc., complete	160	Sqm	1142.81	182849.60
<b>Total</b>					533271.48

Note:- Quantity may vary at the time of execution of work.

Say Rs. 533271/-

(Five Lac Thirty Three Thousand Two Hundred and Seventy One Only)