



Maharaja Ranjit Singh Punjab Technical University
Dabwali Road, Bathinda.

(Established by Govt. of Punjab vide Punjab Act No. 5 of 2015 and approved Under Section 2(f) & 12(B) of UGC)

Ref. No. MRSPTU/Estate/18-19/ 224 to 229

Dated 14-1-19

(Regd.)

To

As per List Attached.

Sub: - Quotations for Renovation of 2 Bathrooms (Room No 6 on G.F & Room No 2 on F.F) of Guest House in the Campus.

Dear Sir,

01. You are requested to quote the rates for the items shown in the Appendix 'A' separately attached to this letter.

02. Following shall be taken note of while quoting the rates:-


- The rates will be F.O.R. MRSPTU, Bathinda.
- Quotation received later than due date are liable to be ignored/rejected.
- Quotation must be submitted on letter head of the firm with all particular, any other format will not be acceptable.
- The quality of the items to be quoted should be best available in the market.
- The envelope must bear the word:-

"QUOTATION FOR " Renovation of 2 Bathrooms (Room No 6 on G.F & Room No 2 on F.F) of Guest House in the Campus.

Enquiry No. As above dated _____
Due on 25-01-2019.

IMPORTANT: -In the absence of information as required under 2(e) above, if an envelope is received & opened inadvertently, the university will not be responsible and the quotation may not be considered even if quoting lowest rates.

03. The quotations duly completed should be in the name of Executive Engineer, MRSPTU, Bathinda and should reach in the office of undersigned by 25-01-2019 up to 03:30 and same shall be opened at 04:00 on same date. Your representative may be present during the opening of the quotations.


Executive Engineer,
MRSPTU, Bathinda.

Copy to:-

1. Incharge, Computer Centre, to upload a copy on university & college websites.
2. Notice Board.
3. Master File

P.T.O.

TERMS & CONDITIONS

1. **DELIVERY PERIOD:-**

Minimum Period for delivery/job completion should be mentioned clearly.

2. **VALIDITY OF QUOTATIONS:-**

Quotations will be considered valid for 03 months from the date of quotation.

3. **GUARANTEE/WARRANTY:-**

Guarantee/Warranty should be mentioned clearly.

4. **DISCOUNT/REBATES:-**

A Special discount/rebate wherever admissible keeping in view that the supplies are being made for education purpose in respect of Public Institution of national importance may please be indicated.

5. **VICE CHANCELLOR'S RIGHTS:**

Vice Chancellor, MRSPTU, Bathinda reserves the rights of acceptance or rejection of any or all quotations. The discretion for increasing or decreasing of the quantities also rests with him. MRSPTU also not bind itself to accept the lowest price. In case of any dispute, the decision of Vice Chancellor, MRSPTU, Bathinda will be final & binding.

6. **SAMPLE/BRAND/MAKE/WEIGHT:-**

Sample where asked for, will invariably be made available and sent along with the quotations. However, Brand/Make/Weight etc. must be mentioned clearly in the quotations. Technical literature/pamphlet should also be enclosed.

7. **REJECTION:-**

Quotation not conforming to the set procedure as above will be rejected.

8. **CORRESPONDANCE:**

No correspondence regarding acceptance/rejection of a quotation will be entertained.

MRSPTU shall not be held responsible for any postal delay in sending or late receipt of quotation. Quotation should be free from corrections & erasures.



Appendix-'A'

**MAHARAJA RANJIT SINGH PUNJAB TECHNICAL UNIVERSITY,
DABWALI ROAD, BATHINDA**

(Established by Govt. of Punjab vide Punjab Act No. 5 of 2015 and approved Under Section 2(f) & 12(B) of UGC)

Renovation of 2 Bathrooms (Room No 6 on G.F & Room No 2 on F.F) of Guest House in the Campus

S. No.	Description of Item	Qty	Unit	Rate
1/8.39	Dismantling of brick work in cement sand mortar/lime mortar including T&P scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material & staking the serviceable material with all lifts & lead of 100 meter (By Mechanical Means)	01.40	Cum.	
2/8.6 (d)	Dismantling cement concrete 1:2:4	1	Cum.	
3/8.16	Dismantling cement conglomerate floors (25 mm to 50 mm) thick including concrete base.	10	Sqm.	
4/8.17	Dismantling cement conglomerate floors (25 mm to 50 mm) thick without concrete base.	50	Sqm.	
5/8.31 c	Scraping cement plaster	10.50	Sqm.	
A	Scraping white wash	20	Sqm.	
6/8.35	Dismantling glazed tiles (to be carefully removed)	48	Sqm.	
7/12.144	Providing and fixing 1 st quality ceramic glazed wall tiles conforming to IS :15622 (thickness to be specified by the manufacture of approved make in all colors, shades except burgundy, bottle green, black of size 300mmx600mm as approved by Engineer-in-charge in skirting, rashers of steps and dados over 12 mm thick bed of cement Mortar 1:4 (1 cement:4 fine sand)and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.	48	Sqm.	
8/14.139	Providing and laying Rectified Porcelain floor tiles 400mmx400mm or more (thickness to be specified by the manufacturer) of premium quality conforming to IS:15622 of approved make in all colors laid on 20 mm thick bed of Cement Mortar 1:4 (1 Cement :4 fine sand) for new flooring or laid with cement based high polymer modified quick set tile adhesive (water based)of approved make IS 15477 marked using 5 kg adhesive per sqm. Of tile are in average 3mm thickness over existing floor, including pointing the joints with white cement and matching pigments etc., complete.	12.00	Sqm.	
9/17.44	Providing and fixing 0.50mm thick aluminum sheet including cost of necessary fittings i.e. screws, etc. complete.	1.70	Sqm.	
10/16.6	Preparation of plastered surfaces for distempering including surface, applying filling with approved quality filler consisting of plaster of Paris and chalk mitti including finishing the surface to the required	65	Sqm	

	finish complete.			
11/16.11	Distempering with Acrylic washable oil bound distemper (of approved manufacture) two coats over one priming coat to give an even shade.	65	Sqm	
12/16.17	Applying pink primer or aluminum priming coat on wood work including preparation of surface knotting and stopping etc.	20	Sqm	
a)	With special quality paint			
13/16.18	Painting two coats excluding priming coat with synthetic enamel paint in all shades on wood work, metallic or plastered, concrete surface to give an even shade.	20	Sqm	
a)	With special quality paint			
14/NS	Supplying & Fixing 12mm thick Toughen Glass for glazing frames	3.5	Sqm	
15/30.37 (iii)	Providing and fixing in position vitreous chinaware white lavatory suites of approved make (to the approval of Engineer-in-charge) consisting of C.P brass waste 32mm dia with one C.P brass pillar tap compete in all respect Size 630mm x 450mm	02	Each	
16/NS	Providing and fixing in position Chinaware European type water closet (L-740mm, W-410mm, H-740mm) with S trap, Centre of outlet 225mm from Wall with flushing wash down inbuilt cistern & Seat cover complete in all respects.	2	No's	
17/30.57 (a)	Providing & Fixing in position paper holders of approved make (to the approval of Engineer-in-charge) fixed into wall with C.P. brass screws complete in all respect C.P. brass toilet paper holder	02	Each	
18/30.58 (a)	Providing and fixing in position towel rails/ ring of approved make (to the approval of Engineer-in-charge) fixed in with rawl plugs embedded in walls with brass screws compete in all respect C.P brass towel Rails size 15mm dia 600mm long	02	Each	
19/30.64 A)	Providing & Fixing in position C.P. Brass flange of approval make (to the approval of the Engineer-in-charge) under various fixtures complete in all respects	20	Each.	
20/30.64 B)	Providing & Fixing in position C.P. Brass extension piece 25mm long or 50mm long of approval make (to the approval of the Engineer-in-charge) with various fixtures complete in all respects	10	Each	
21/30.65 a) i)	Providing & Fixing in position 15mm i/d bib cock of approved make (to the approval of Engineer-in-charge) complete in all respects C.P. Brass bib cock long nose/ long body without flange	05	No's	
22/30.67 (a)	Providing & Fixing in position liquid soap container of approved make (to the approval of Engineer-in-charge) complete in all respects C.P. brass liquid soap container	02	Each	
23/30.73	Providing & fixing in position C.P. Copper tube connection of	05	Each	

(c)	approved make (to the approval of Engineer-in-charge) complete in all respects C.P. copper tube connection of size 15 mm x 450 mm with C.P. Brass nut			
24/30.86 (a)	Dismantling H.C.I Soil pipes including disposal as desired by the Engineer-in-Charge. 100mm i/d H.C.I. pipe	05	Meter	
25/15.9	12.5 mm thick plaster 1:4	15.15	Sqm.	
26/18.25 (b)	Supplying and fixing glass panes with glazing clips and special metal sash putty of approved make. Glass panes 4mm thick above 0.40 sqm area.	05	Sqm.	
27/18.4	Wrought iron and mild steel ladders, framed grills, grating etc. with ends of bars, riveted or welded or forged, framed window guards, barred iron doors, stair case, iron railing including cost of bolts and nuts or screws or welding rod, complete fixed in position.	0.50	Qtl.	
28/28.36 a) b)	Providing and laying, jointing, fixing, testing ISI Marked G.I. Pipe (as per IS 1239) B- class, premium make such as (Jindal Hisar) including cost of Specials such as tees, bends, sockets, elbow etc. cutting, threading and testing in trenches in the ground complete. 15mm i/d 20mm i/d	15 10	Mtr Mtr	
29/28.40 a) b)	Providing, Fixing and jointing G.I. Union Coupling (of approved make with the approval of Engineer-in-charge) as per IS 1879 in G.I. pipe lines complete in all respect 15mm i/d G.I union 20mm i/d G.I union	02 02	No's No's	
30/28.43 b)	Providing, fixing and jointing ISI Marked Gun-Metal peet valves (Heavy Pattern) as per IS 778 with hand wheels, on G.I. pipe lines laid in the ground or inside buildings including all carriages complete. 20mm i/d Gun metal peet valve heavy pattern	02	No's	
31/28.56 b)	Cutting holes upto 23cm square through B.B. in cement walls or stone masonry wall in cement for pipes, and making good the same 7 finishing according to existing finish where required. Through wall 22.88 cm thick	02	No's	
32/30.85 c)	Cutting chase in brick walls in cement or in floor for embedding G.I or C.I pipes line and making good the same to its original condition Size 75mm x 50mm	30	Mtr	
33/14.150	Baroda green marble flooring 15mm to 20mm thick over 12.5 mm thick base of Cement mortar 1:3 laid and jointed with white cement slurry with pigment to match the shade of marble including rubbing & Polishing.	04	Sqm	

34 10.33	Nicking cement concrete surface (Over 28 days old including preparation and laying slurry).	11.50	Sqm	
35 18.27	Wire gauge fixed on steel windows of standard rolled steel section, with 3mm thick flat iron cover moulding of 12.5mm width, fixed with machine screws, complete in all respects.	05	Sqm	

NOTE:

1. Any error regarding description, reference to CSR quantity, rate, premium, unit calculations omission, addition will be corrected at any stage as per CSR, AOR, specifications and drawings and no claim whatsoever shall be entertained on this account.
2. Quantity may vary at the time of execution of work.

Specifications Checked & Verified.


 Executive Engineer,
 MRSPTU, Bathinda.