



Maharaja Ranjit Singh Punjab Technical University
Dabwali Road, Bathinda.

(Established by Govt. of Punjab vide Punjab Act No. 5 of 2015 and approved Under Section 2(f) & 12(B) of UGC)

Ref. No. MRSPTU/Estate/25-26/ 072-79

Dated 12/01/2026

(Regd.)

To

As per List Attached.

Sub: - Quotations for Repair of false ceiling in Lecture Theatre LT-308 & Multipurpose Hall of MRSPTU, Bathinda.

Dear Sir,

01. You are requested to quote the rates for the items shown in the Appendix 'A' separately attached to this letter. The rate must be quoted only on the attached paper as per our specifications.
02. Following shall be taken note of while quoting the rates:-
 - a) The rates will be F.O.R. MRSPTU, Bathinda.
 - b) Job Completion period should be mentioned clearly.
 - c) Warranty/Guarantee/All contractual obligations should be mentioned clearly.
 - d) Payment will be made after successful inspection of the team.
 - e) For research items, the relevant exemption certificate DSIR will be issued to the successful firm to charge GST @5% only, if applicable, otherwise GST will be charged at applicable rates.
 - f) Quotation received later than due date are liable to be ignored/rejected.
 - g) Quotation must be submitted on **LETTER HEAD** of the firm in the name of **REGISTRAR, MRSPTU, BATHINDA** with all particularly duly signed with stamp in sealed envelope, any other format will not be acceptable.
 - h) The envelope must bear the word:-
QUOTATION FOR " Repair of false ceiling in Lecture Theatre LT-308 & Multipurpose Hall of MRSPTU, Bathinda."
Enquiry No. _____ As above dated _____
Due on _____
Address: As mentioned as point no. 04
IMPORTANT: -In the absence of information as required under 2(h) above, if an envelope is received & opened inadvertently, the university will not be responsible and the quotation may not be considered even if quoting lowest rates.
 - i) Please mention any other charges/conditions
 - j) Loose, tempered or incomplete quotation will not be considered.
 - k) Any other information as per requirement of indentor/department.
 - l) The quality of the items to be quoted should be best available in the market.
03. General Terms & Conditions are attached along with.
04. The quotations should reach the office of Registrar, Maharaja Ranjit Singh Punjab Technical University, Bathinda-151001 by 28-01-2026 up to 5 pm and same shall be opened there after in the presence of Committee members.

Indentor

Head of Department

Copy to:-

- ✓ Professor Incharge, IT Enabled Services, MRSPTU, Bathinda to upload a copy on University & College Websites.

TERMS & CONDITIONS

1. **JOB COMPLETION PERIOD:-**
Minimum Period for delivery/job completion should be mentioned clearly.
2. **VALIDITY OF QUOTATIONS:-**
Quotations will be considered valid for 03 months from the date of quotation.
3. **GUARANTEE/WARRANTY:-**
Guarantee/Warranty should be mentioned clearly.
4. **DISCOUNT/REBATES:-**
A Special discount/rebate wherever admissible keeping in view that the supplies are being made for education purpose in respect of Public Institution of national importance may please be indicated.
5. **VICE CHANCELLOR'S RIGHTS:**
Vice Chancellor, MRSPTU, Bathinda reserves the rights of acceptance or rejection of any or all quotations. The discretion for increasing or decreasing of the quantities also rests with him. MRSPTU also not bind itself to accept the lowest price. In case of any dispute, the decision of Vice Chancellor, MRSPTU, Bathinda will be final & binding.
6. **SAMPLE/BRAND/MAKE/WEIGHT:-**
Sample where asked for, will invariably be made available and sent along with the quotations. However, Brand/Make/Weight etc. must be mentioned clearly in the quotations. Technical literature/pamphlet should also be enclosed.
7. **REJECTION:-**
Quotation not conforming to the set procedure as above will be rejected.
8. **CORRESPONDENCE:**
No correspondence regarding acceptance/rejection of a quotation will be entertained.

MRSPTU shall not be held responsible for any postal delay in sending or late receipt of quotation. Quotation should be free from corrections & erasures.

QUOTATION

To

The Registrar,
MRSP TU, Bathinda.

Sub: Repair of False Ceiling in Lecture Theatre LT-308 & Multipurpose Hall of MRSP TU, Bathinda.

S.No./ CSR Ref	Item Description/ Specification	Unit	Qty.	Basic Rate (per unit in Rs.)	Disco unt/C SR +/-, (if any)	GST (in %age) (if applic able)	Rate (includ ing GST/ discou nt)	Total Amount Including GST/Disc ount/CSR +/-)
1/8.44	Dismantling aluminium/Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by Engineer-in-Charge	Sqm	6					
2/13.65	Providing and Fixing ceiling consisting of 12.5mm thick Gypsum Board of any size G.I. Cradling hanged from the ceiling by means of G.I. hanger complete as per drawings, specifications and to the entire satisfaction of engineer-in-charge. (Through Rate)	Sqm	30					
3/13.64	Providing and fixing mineral fibre ceiling tiles at all heights With 16mm thick beveled tegular mineral fibre Anti-microbial false ceiling tile of size 595x595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflection >85%, Thermal Conductivity $k=0.052 - 0.057$ w/m K, Fire Performance as per (BS 476 pt-6 & 7) in true horizontal level suspended on interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32mm of length 3000mm, cross T of size 15x32mm of length 1200mm and secondary intermediate cross T of size 15x32mm of length 600mm to form grid module of size	Sqm	76					

	<p>600x600mm suspended from ceiling using galvanized mild steel item (galvanized @80gsm) 50mm long 8mm outer diameter M-6 dash fasteners, 6mm diameter fully threaded hanger rod up to 1000mm length and L-shape level adjuster of size 85x25x2 mm, spaced at 1200mm centre to centre along main 'T'. The system should rest on periphery walls/partitions with the help of GI Perimeter wall angle of size 24x24x3000 mm made of 0.40mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450mm centre to centre & 40mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights. The works shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge. (Through Rate)</p>							
3/13.64	<p>Providing and fixing mineral fibre ceiling tiles at all heights With 16mm thick beveled tegular mineral fibre Anti-microbial false ceiling tile of size 595x595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflection >85%, Thermal Conductivity k=0.052 – 0.057 w/m K, Fire Performance as per (BS 476 pt-6 & 7) in true horizontal level suspended on interlocking T-Grid of hot dipped all round galvanized iron section of 0.33 mm thick (galvanized @120 gsm) comprising of main T runners of 15x32mm of length 3000mm, cross T of size 15x32mm of length 1200mm and secondary intermediate cross T of size 15x32mm of length 600mm to form grid module of size 600x600mm suspended from ceiling using galvanized mild steel item (galvanized @80gsm) 50mm long 8mm outer diameter M-6 dash fasteners, 6mm diameter fully threaded hanger rod up to 1000mm length and L-shape level adjuster of size 85x25x2 mm, spaced at</p>	Sqm	8					

	1200mm centre to centre along main 'T'. The system should rest on periphery walls/partitions with the help of GI Perimeter wall angle of size 24x24x3000 mm made of 0.40mm thick sheet, to be fixed to the wall with help of plastic rawl plug at 450mm centre to centre & 40mm long dry wall S.S. screws. The exposed bottom portion of all T-sections used in false ceiling support system shall be pre-painted with polyester baked paint, for all heights. The works shall be carried out as per specifications, drawings and as per directions of the engineer-in-charge. (Labour Rate)							
4/16.15	Preparation of plywood surface for painting including sand papering the surface and applying filling with approved quality fillers consisting of white lead, linseed oil, Varnish, and Chalk Mitti including finishing the surface to required finish complete	Sqm	30					
5/16.63	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (two or more coats)	Sqm	30					

Note: 1) University GST No. 03AAAGT0124M1ZJ.

2) Quantity may vary at the time of execution of work.

3) The University shall not be held responsible for any incident/ mishappening /accident that may occur during the execution of work.

4) The above rates have inclusive of all implements, labour, material etc. required for execution of work.

General Conditions:

- The rates will be F.O.R. (Estate Deptt.) MRSPTU, Bathinda.
- Job Completion period should be mentioned clearly.
- Warranty/Guarantee/All Contractual Obligations should be mentioned clearly.
- Any other.

Name of Bidder _____

Signature with Stamp _____